

## WORK PROJECT EXAMPLES

Yes, time and expense for work done on your cabin/home can be entered.

### Building specific project examples

1. Chimney spark arrestor installation
2. Repairs to retrofit open-eaves style construction to soffited-eaves
3. Modifications of deck to increase the gap between boards from  $\frac{1}{8}$  inch to  $\frac{1}{4}$  inch
4. Inspection of roof; replacement of shingles as needed
5. Inspection/repairs of eaves and soffits to ensure construction materials are in good condition
6. Removal all flammable materials from under decks and porches
7. Removal of debris between deck board gaps/joints
8. Removal of debris on the roof and in the gutters as needed
9. Replacement of missing deck boards to reduce ember entry to area under decks
10. Replacement of vinyl gutters with metal gutters
11. Replacement of wood fencing sections where attached to the house with a noncombustible product
12. Resident or contractor labor to perform ignition resistant exterior improvements (e.g., new Class A roofs, mesh screening added to attic and crawl space vents, siding repairs, replacement of wood fencing attached to siding, etc.)
13. Installation of weather stripping along the perimeter of garage doors to help keep embers out
14. Use of a sealant (such as caulking) to cover gaps in open-eave areas

### Vegetation specific project examples

15. Clearing of debris at the base of combustible fences
  16. Clearing of vegetation beneath and around large stationary propane tanks
  17. Creation of a permanent non-flammable footprint under large stationary propane tanks
  18. Creation of a non-flammable footprint under decks with gravel, stone or concrete
  19. Creation of small fuel breaks by adding hardscaping (e.g., driveways, walkways/paths, patios, stone walls, etc.)
  20. Delimiting and removal of lower tree branches
  21. Relocation of firewood piles to at least 30 feet from cabins/homes and other structures
  22. Mowing lawns and trimming native grasses and weeds as needed
  23. Raking and removal of pine needles, leaves, and ground debris
  24. Replacement of combustible mulch material with stone/gravel
  25. Replacement of highly-flammable vegetation with fire-resistant species
  26. Reduction of ladder fuels
  27. Stacking/piling of slash and other debris for chipping or curbside pickup
  28. Thinning or removal of trees
  29. Debris removal and maintenance of commonly owned areas
  30. Reduction of vegetation/fuels from adjacent ingress and egress routes
-